



Vaidyaratnam P.S.Varier's

## ARYA VAIDYA SALA, KOTTAKKAL

### Schedule of Re-Tarring works at Various areas at AVS Kottakkal

Sl No	Description	Quantity	Unit	Rate In figures and words	Amount
<b>A CHARITABLE HOSPITAL INTERNAL ROAD AND PARKING AREA</b>					
1	Patch work the existing WBM road with 36/ 20 mm hard granite brocken stone and sufficient quantity melted bitumin (additional quantity of suitable size aggregate if required should supply by the contractor ) with proper line and gradient after cleaning the surface with wire brush/ compressed air.The work including Rolling with a three wheel 80-100 KN static capacity roller , finished to required level and grade etc. complete. (Observed data ) as per recent CPWD specifications.	1450.00	Sq.Mtr.		
2	20mm thick premix carpet surfacing with 3.5 cum and 1.8 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively, per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively including a tack coat with hot straight run bitumen (RS-1), including consolidation with road roller of 80-100 KN static capacity etc. complete With paving Asphalt grade VG - 30 heated and then mixed with solvent at the rate of 70 grams per kg of asphalt as per recent CPWD specifications	2750.00	Sq.Mtr.		
3	Providing and laying seal coat over prepared surface of road with bitumen heated in bitumen boiler fitted with the spray set spraying using 98 kg of bitumen of grade VG - 30 and blinding surface with 0.90 cum of stone aggregate of 6.7 mm size (Passing 11.2 mm sieve and retained on 2.36 mm sieve) per 100 sqm of road surface including rolling and finishing with power road roller all complete.	2750.00	Sq.Mtr.		
4	60cm dia convex mirrors including fixing with suitable bracket or post in T junction	1.00	Nos	..	
	Total				
	Add CGST (.....)				
	Add SGST (.....)				
	Total (A)				

Sl No	Description	Quantity	Unit	Rate In figures and words	Amount
<b>B</b>	<b>PARKING YARD IN FRONT OF KAILASAMANDIAM</b>				
1	Patch work the existing WBM road with 36/ 20 mm hard granite broken stone and sufficient quantity melted bitumin (additional quantity of suitable size aggregate if required should supply by the contractor ) with proper line and gradient after cleaning the surface with wire brush/ compressed air.The work including Rolling with a three wheel 80-100 KN static capacity roller , finished to required level and grade etc. complete. (Observed data ) as per recent CPWD specifications.	15.00	Sq.Mtr.		
2	20mm thick premix carpet surfacing with 3.5 cum and 1.8 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively, per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively including a tack coat with hot straight run bitumen (RS-1), including consolidation with road roller of 80-100 KN static capacity etc. complete With paving Asphalt grade VG - 30 heated and then mixed with solvent at the rate of 70 grams per kg of asphalt as per recent CPWD specifications	600.00	Sq.Mtr.		
3	Providing and laying seal coat over prepared surface of road with bitumen heated in bitumen boiler fitted with the spray set spraying using 98 kg of bitumen of grade VG - 30 and blinding surface with 0.90 cum of stone aggregate of 6.7 mm size (Passing 11.2 mm sieve and retained on 2.36 mm sieve) per 100 sqm of road surface including rolling and finishing with power road roller all complete.	600.00	Sq.Mtr.		
4	60cm dia convex mirrors including fixing with suitable bracket or post in T junction	1.00	Nos		
	Total				
	Add CGST (.....)				
	Add SGST (.....)				
	Total (B)				

Sl No	Description	Quantity	Unit	Rate In figures and words	Amount
<b>C</b>	<b>HEAD OFFICE FRONT YARD</b>				
1	Patch work the existing WBM road with 36/ 20 mm hard granite broken stone and sufficient quantity melted bitumin (additional quantity of suitable size aggregate if required should supply by the contractor ) with proper line and gradient after cleaning the surface with wire brush/ compressed air.The work including Rolling with a three wheel 80-100 KN static capacity roller , finished to required level and grade etc. complete. (Observed data ) as per recent CPWD specifications.	80.00	Sq.Mtr.		
2	20mm thick premix carpet surfacing with 3.5 cum and 1.8 cum of stone chippings of 13.2 mm size and 11.2 mm size respectively, per 100 sqm and 52 kg and 56 kg of hot bitumen per cum of stone chippings of 13.2 mm and 11.2 mm size respectively including a tack coat with hot straight run bitumen (RS-1), including consolidation with road roller of 80-100 KN static capacity etc. complete With paving Asphalt grade VG - 30 heated and then mixed with solvent at the rate of 70 grams per kg of asphalt as per recent CPWD specifications	600.00	Sq.Mtr.		
3	Providing and laying seal coat over prepared surface of road with bitumen heated in bitumen boiler fitted with the spray set spraying using 98 kg of bitumen of grade VG - 30 and blinding surface with 0.90 cum of stone aggregate of 6.7 mm size (Passing 11.2 mm sieve and retained on 2.36 mm sieve) per 100 sqm of road surface including rolling and finishing with power road roller all complete.	600.00	Sq.Mtr.		
4	60cm dia convex mirrors including fixing with suitable bracket or post in T junction	1.00	Nos		
	Total				
	Add CGST (.....)				
	Add SGST (.....)				
	Total (C)				
	Grand Total (A+B+C)				
(Rupees ..... only)					

Date:

Name,signature &amp; Address of the Contractor