

Vaidyaratnam P.S.Varier's
ARYA VAIDYA SALA, KOTTAKKAL

Schedule- Re - roofing the GI powder coated trafford sheet with addl. purlins
at MMH Block of Charitable Hospital.

Sl. No	Description of items	Quantity	Unit	Rate In figures and words	Amount
1	Supplying and fixing 80mm dia,3.2mm thick MS pipe for purlins between the existing purlins with necessary welding, cutting, cleats, screws, necessary end capping , including painting two coat enamel paint over one coat zincromite iron primer etc.. (approx. quantity- 1300 M) and Roofing with GI powder coated trafford sheet (JSW or equivalent) 0.4mm thick (Terracoata Colour), fixing with necessary self screws/J-bolt, roofing compound washers,plate washers etc (Approx. quantity-2300 Sq.M) along with the ridge and valley gutter with powder coated GI plain sheet 90cm wide wherever necessary to assure the water tightness of the whole structure (Approx.Quantity 300 M) and the scope includes dismantling and removing the existing roofing sheets , lowering, stacking the material care fully for reuse within a distance of 150m, the all above work scope includes temporary protection of roof area against rain fall if necessary, and without damaging the existing structure , the rate including cost and conveyance of all material, headload lifting and lowering, scaffolding and labour charges etc.complete as per the instruction of SE..(The measurements should taken for new sheet area only)	2,300	Sq.M		
2	Supplying and fixing UPVC Rain water gutter square or trapezoidal shape of 8" size (Star or Equivalent) with necessary brackets @ 75cm C/C with required slope and line (Approx.quantity - 300M) and connecting it with various dia rainwater down pipe to the existing rainwater pipe including painting with matching colour and connection brackets (Lumpsum quantity). the above work scope includes cost and conveyance of all materials, labour charges, scaffolding, head load and lifting etc. complete as per the instruction of SE.(The measurements should taken for new gutter length only)	300	M		

Sl. No	Description of items	Quantity	Unit	Rate In figures and words	Amount
3	Painting with Enamel paint two coats over the existing M.S structures after the proper cleaning the rate includes the cost of all material, labour, scaffolding etc. complete	5,000	RM		
4	Removal of existing damaged gypsum ceiling and replace with new gypsum board false ceiling (Gyproc or equivalent) and applying two coats of interior emulsion paint (Reputed brand such as Asian or equivalent) matching to the existing size & colour including primer coat and necessary putty work, joint tape etc. The above work scope includes cost of all material, labour, scaffolding, shifting of all debris such as damaged gypsum board to outside the AVS premises etc complete (The measurements should taken for new gypsum area only)	150	Sq.M		
	Total				
	Add CGST 9%				
	Add SGST 9%				
	Grand Total				
	Grand Total				
	(Rupees only)				